

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 1 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "A" SITE PREPARATION					
1	Mobilization (includes bonds insurance and demobilization)		1	L.S.		
2	Traffic control	S.P.	1	L.S.		
3	Pre-construction Survey	S.P.	1	L.S.		
4	Temporary fencing (MODU-LOC or equivalent)	S.P.	1	L.S.		
5	Erosion and sediment control	S.P.	1	L.S.		

SUB-TOTAL PART "A" _____

TENDERER'S INITIALS _____

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "B" REMOVALS (to be disposed off-site)					
1	Remove and dispose off-site existing watermain pipe including removal of V&VB and hydrants	510 & S.P.	622	m		
2	Remove existing water services and dispose off-site	510 & S.P.	35	each		
3	Grind and dispose at 1560 Laurier Street existing top lift of asphalt - 50mm thick	510 & S.P.	7447	m ²		
4	Sawcut, remove & dispose off-site existing asphalt over watermain and service trench	510 & S.P.	3107	m ²		
5	Remove existing street signs	510 & S.P.	10	each		

SUB-TOTAL PART "B" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 1 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "C" WATERMAIN					
1	Install temporary watermain	441 & S.P.				
	i) Main		1	L.S.		
	ii) 19mm dia. water service		29	each		
	iii) 25mm dia. water service		3	each		
	iv) 40mm dia. water service		1	each		
	v) 50mm dia. water service	1	each			
2	Connect to existing watermain	441 & S.P.				
	i) Connect to existing 300 mm dia. watermain at the intersection of St-Joseph Street & Laurier Street. (on Laurier at STA 3+377)		1	each		
	ii) Connect to existing 300 mm dia. watermain at the intersection of St-Joseph Street & Laurier Street. (on Pouliotte)		1	each		
	iii) Connect to existing 150 mm dia. watermain service at the Rockland Fire Station. (On Laurier Street at STA 3+560)		1	each		
	iv) Connect to existing 250 mm dia. watermain at the intersection of Henri Circle & Laurier Street. (On Laurier Street at STA 3+960)	1	each			
3	Supply and install watermain pipe PVC DR 18 CLASS 150 c/w nitrine gaskets and road reinstatement - 450mm granular "B", 150mm granular "A", and 2x40mm HL8	310, 314, 441 & S.P.				
	i) 300mm dia.		594	m		
4	Supply and install valve and valve box	441 & S.P.				
	i) 300mm dia.		4	each		
5	Supply and install fire hydrant c/w valve, valve box and lead	441 & S.P.	8	each		
	PROVISIONAL ITEMS					
6	Subexcavation for trench	S.P.	30.0	m ³		

SUB-TOTAL PART "C" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 1 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "D" SERVICES					
1	Supply and install a PEX water service c/w standpost and road granular reinstatement - 450mm Granular 'B', 150mm Granular 'A', and 2x40mm HL8	310, 314, 410, 441 & S.P.				
	i) North side - 19mm dia. Service		10	each		
	ii) North side - 25mm dia. Service		1	each		
	iii) North side - 40mm dia. Service		1	each		
	iv) North side - 50mm dia. Service		1	each		
	v) South side - 19mm dia. Service		19	each		
	ii) South side - 25mm dia. Service		2	each		
2	Supply and install a 150mm dia. PVC water service c/w V&VB and road granular reinstatement - 450mm Granular 'B', 150mm Granular 'A', and 2x40mm HL8	310, 314, 410, 441 & S.P.	1	each		
	PROVISIONAL ITEMS					
3	Lateral sanitary service repair	410 & S.P.	13	each		
4	Lateral storm service repair	410 & S.P.	13	each		
5	Hydrovac		20	hrs		

SUB-TOTAL PART "D" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 1 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "E" REINSTATEMENT					
1	Remove Existing 1.5m sidewalk and build new 1.5m sidewalk at services and Fire Hydrant locations.	510, 351 & S.P.	66	m ²		
2	Remove Existing 1.5m monolithic sidewalk and build new 1.5m monolithic sidewalk at services and Fire Hydrant locations.	510, 351 & S.P.	205	m ²		
3	Remove existing barrier curb and build new curb at services and Fire Hydrant locations.	510, 353 & S.P.	44	m		
4	Remove existing interlock, stack interlock and reinstall at services and Fire Hydrant locations.	510, 355 & S.P.	44	m ²		
5	Driveway reinstatement					
	i) Asphalt		30	m ²		
	ii) Gravel		30	m ²		
	iii) Interlock		30	m ²		
6	Tops oil (100mm) and sod on Laurier Street	802 & S.P.	80	m ²		
7	Line painting					
	i) Yellow and white lines	710	2000	m		
	ii) Stop bar		6	each		
8	50mm HL3 c/w road cleaning, tack coat and grinding keys	310 & S.P.	962	tonne		
9	Retaining wall		1	L.S.		
10	Fence		1	L.S.		
11	Reinstallation of street signs		10	each		

SUB-TOTAL PART "E" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 2 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "A" SITE PREPARATION					
1	Mobilization (includes bonds insurance and demobilization)		1	L.S.		
2	Traffic control	S.P.	1	L.S.		
3	Pre-construction Survey	S.P.	1	L.S.		
4	Temporary fencing (MODU-LOC or equivalent)	S.P.	1	L.S.		
5	Erosion and sediment control	S.P.	1	L.S.		

SUB-TOTAL PART "A" _____

TENDERER'S INITIALS _____

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "B" REMOVALS (to be disposed off-site)					
1	Remove and dispose off-site existing watermain pipe including removal of V&VB and hydrants	510 & S.P.	341	m		
2	Remove existing water services and dispose off-site	510 & S.P.	29	each		
3	Grind and dispose at 1560 Laurier Street existing top lift of asphalt - 50mm thick	510 & S.P.	3764	m ²		
4	Sawcut, remove & dispose off-site existing asphalt over watermain and services trench	510 & S.P.	1733	m ²		
5	Remove existing street signs	510 & S.P.	10	each		

SUB-TOTAL PART "B" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 2 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "C" WATERMAIN					
1	Install temporary watermain					
	i) Main	441 & S.P.	1	L.S.		
	ii) 19mm dia. service		25	L.S.		
	iii) 25mm dia. service		1	L.S.		
	iv) 38mm dia. service		1	each		
2	Connect to existing watermain					
	i) Connect to existing 200mm dia. watermain at the intersection of Laurier Street & Giroux Street. (on Laurier)	441 & S.P.	1	each		
	ii) Connect to existing 200mm dia. watermain at the intersection of Laurier Street & Giroux Street. (on Giroux)		1	each		
	iii) Connect to existing 150 mm dia. watermain at the intersection of Laurier Street & Edwards Street. (on Edwards)		1	each		
	iv) Connect to existing 200 mm dia. watermain at the intersection of Laurier Street & Edwards Street. (on Edwards)		1	each		
	v) Connect to existing 150 mm dia. watermain at the intersection of Powers Street & Laurier Street.		1	each		
	vi) Connect to existing 300mm dia. watermain at the intersection of Laurier Street & Gareau Street. (on Laurier at STA 3+335)		1	each		

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 2 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "C" WATERMAIN (CONT'D)					
3	Supply and install watermain pipe PVC DR 18 CLASS 150 c/w nitrine gaskets and road reinstatement - 450mm granular "B", 150mm granular "A", and 2x40mm HL8	310, 314, 441 & S.P.				
	i) 150mm dia.		9	m		
	ii) 200mm dia.		15	m		
	iii) 300mm dia.		318	m		
4	Supply and install valve and valve box					
	i) 150mm dia.	441 & S.P.	1	each		
	ii) 200mm dia.		1	each		
	iii) 300mm dia.		7	each		
5	Supply and install fire hydrant c/w valve, valve box and lead	441 & S.P.	3	each		
	PROVISIONAL ITEMS					
6	Subexcavation for trench	S.P.	15	m ³		

SUB-TOTAL PART "C" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 2 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "D" SERVICES					
1	Supply and install a PEX water service c/w standpost and road granular reinstatement - 450mm Granular 'B', 150mm Granular 'A', and 2x40mm HL8	310, 314, 410, 441 & S.P.				
	i) North side - 19mm dia. service		16	each		
	ii) South side - 19mm dia. service		9	each		
	iii) South side - 25mm dia. service		2	each		
	iv) South side - 38mm dia. service		1	each		
	PROVISIONAL ITEMS					
2	Lateral sanitary service repair	410 & S.P.	16	each		
3	Lateral storm service repair	410 & S.P.	16	each		
4	Hydrovac		20	hrs		

SUB-TOTAL PART "D" _____

TENDERER'S INITIALS _____

ADDENDUM #2
SCHEDULE OF PRICES - PHASE 2 CONTRACT

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "E" REINSTATEMENT					
1	Remove Existing 1.5m sidewalk and build new 1.5m sidewalk at services and Fire Hydrant locations.	510, 351 & S.P.	180	m ²		
2	Remove Existing 1.5m monolithic sidewalk and build new 1.5m monolithic sidewalk at services and Fire Hydrant locations.	510, 351 & S.P.	35	m ²		
3	Remove existing barrier curb and build new curb at services and Fire Hydrant locations.	510, 353 & S.P.	120	m		
4	Remove existing interlock, stack interlock and reinstall at services and Fire Hydrant locations.	510, 355 & S.P.	120	m ²		
5	Driveway reinstatement					
	i) Asphalt		30	m ²		
	ii) Gravel		30	m ²		
	iii) Interlock		30	m ²		
6	Topsil (100mm) and sod on Laurier Street	802 & S.P.	60	m ²		
7	Line painting					
	i) Yellow and white lines	710	110	m		
	ii) Stop bar		5	each		
8	50mm HL3 c/w road cleaning, tack coat and grinding keys	310 & S.P.	486	tonne		
9	Retaining wall		1	L.S.		
10	Fence		1	L.S.		
11	Reinstallation of street signs		10	each		

SUB-TOTAL PART "E" _____

TENDERER'S INITIALS _____

ADDENDUM #2

“PHASE 1 Contract”

PART "A" – SITE PREPARATION	\$	_____
PART "B" – REMOVALS	\$	_____
PART "C" – WATERMAIN	\$	_____
PART "D" – SERVICES	\$	_____
PART "E" – REINSTATEMENT	\$	_____
“PHASE 1 CONTRACT” – SUB-TOTAL TENDER PRICE (EXCLUDING ALL TAXES)		=====

“PHASE 2 Contract”

PART "A" – SITE PREPARATION	\$	_____
PART "B" – REMOVALS	\$	_____
PART "C" – WATERMAIN	\$	_____
PART "D" – SERVICES	\$	_____
PART "E" – REINSTATEMENT	\$	_____
“PHASE 2 CONTRACT” – SUB-TOTAL TENDER PRICE (EXCLUDING ALL TAXES)		=====

**“PHASE 1 and PHASE 2 CONTRACTS”
TOTAL TENDER PRICE (EXCLUDING ALL TAXES)**

=====

THE CONTRACTOR SHALL TRANSFER THE TENDER PRICE TO SECTION 4.6 OF THIS DOCUMENT