



**Clarence-Rockland  
CORPORATION  
de la Cité de/ of the City of  
CLARENCE-ROCKLAND**

**ADDENDUM #1**  
3/23/2021 12:53

**2021-011**

**Tender Number**

**Waterworks & Laurier Street Paving**

Request for Proposals Issued On:  
February 26, 2021

Proposal Submission Deadline: 2:00:00 P.M. Local Time in Clarence-Rockland Ontario, Canada On.  
April 8, 2021

**THE INFORMATION CONTAINED IN THIS DOCUMENT IS TIME SENSITIVE**

Please note: This addendum is to be considered part of the above noted Request for Proposal/Tender as though included with the original version. This addendum does not affect the closing date/time. Bidders should acknowledge receipt of all Addendum / Addenda by inserting in the space provided on the Bid Submission Form, the numbers of all Addendum / Addenda received during the bidding period.

**QUESTION REQUESTING CLARIFICATION**

The following questions were received:

<b>1</b>	<b>Question:</b> It appears Part "A"-Site Preparation" is missing from Phase 1 (2021 Construction Season) Schedule of Prices.
	<b>Reply:</b> a) Phase 1 - Part "A" - Site Preparation was omitted. The form of tender shall be completely replaced by the attached form of tender.
<b>2</b>	<b>Question:</b> Should we assume that the asphalt reinstatement quantities for the watermain trench and service trenches (m2) are the same as the m2 provided for the removals in Item 1-804 and 2-804?
	<b>Reply:</b> Phase 1 & 2 - Part "B" - Removals - Item 4: The priced area of asphalt reinstatement of base course will be 4.0m wide times the length of the trench under the asphalt. No additional payment will be made.
<b>3</b>	<b>Question:</b> Can you provide the existing size of sanitary and storm services for Items 1-D03, 1-D04, 2-D03, and 2-D04?
	<b>Reply:</b> Phase 1 & 2 - Part "D" - Services - Items 3 & 4: The existing size of the sanitary and storm laterals shall be assumed to be between 100mm and 150mm in diameter. In the case where the service size would differ from the above-mentioned range, then, the cost will be negotiated with the contractor.
<b>4</b>	<b>Question:</b> Can you provide some more information on the temporary fire hydrants? Spec, make, etc.?
	<b>Reply:</b> Phase 1 & 2 - Part "C" - Watermain - Item 1: No temporary fire hydrants will be required. The contractor shall coordinate all operations regarding the existing fire hydrants with City representatives. The contractor shall also clearly indicate each inoperative hydrant and cover them.
<b>5</b>	<b>Question:</b> Should the reinstatement of all existing hatching, arrows, parking spots, and no parking markings be included in the line painting items?
	<b>Reply:</b> Phase 1 & 2 - Part "E" - Reinstatement - Item 7: The yellow and white lines quantity includes all existing hatching, arrows, centreline, parking spots, etc. Stop bars are on a separate item.
<b>6</b>	<b>Question:</b> Please confirm bonding amounts for labor and material and performance. Performance bond says fifty in words but 100% in numbers...
	<b>Reply:</b> The required bonding for labour and material is 100% as stated under this item. "Upon execution of the contract, the successful bidder will be required to submit Performance Security in the amount of fifty percent (50%) of the contract price pre-tax." Should read "Upon execution of the contract, the successful bidder will be required to submit Performance Security in the amount of one hundred percent (100%) of the contract price pre-tax."
<b>7</b>	<b>Question:</b> Where is the retaining wall for item E9 phase 1 and 2? What type of material, what size of wall is it? Specs mention if retaining wall is to be replaced that a price will be negotiated but there is a lump sum tender item for it? We would need more information on the existing retaining wall in order to provide a price for it.
	<b>Reply:</b> Phase 1 & 2 - Part "E" - Reinstatement - Item 9 & 10 (retaining walls & fences): The contractor shall protect the walls and fences. In the event where the contractor is to damage or remove part of the walls/fences then the reinstatement shall be paid under Part "E" - Item 9 and Part "E" - Item 10 respectively, in the event where the contractor manages to protect all walls/fences, then these two (2) specific items will be paid the full amount regardless of the required effort. The payment will compensate for the effort to protect such structures.
<b>8</b>	<b>Question:</b> Same for item E10 phase 1 and 2, what type of fence, where is this located? Would need more info on fence in order to price.
	<b>Reply:</b> Same reply to question #7.
<b>9</b>	<b>Question:</b> Phase 2, is there supposed to be a new lead for an existing hydrant near corner of Laurier and Power? Removals show that hydrant to be removed but there seems to be a bold line leading to it for new work? is there a new Hydrant going there? if so the number of Hydrants should be 4 not 3...
	<b>Reply:</b> Existing hydrant at the corner of Laurier Street and Powers Street - It shall be removed but not reinstalled as per plan and tender. The line on the hydrant lead should not be bold on the plan.
<b>10</b>	<b>Question:</b> Are we replacing the valve only on Gareau or is it new pipe up to the valve? Connection seems to be on Laurier at station 3+335 but the waterline is bold all the way to the valve on Gareau at station 3+342... Please confirm.
	<b>Reply:</b> The valve at Gareau Street shall be changed and the 300mm diameter watermain on Laurier Street shall be connected directly on the existing 300mm diameter watermain. A piece of 300mm has been installed on Laurier Street a few years ago between Gareau Street and St-Joseph Street. It explains why this piece of watermain is not being replaced.
<b>11</b>	<b>Question:</b> Where is the 150mm service for Phase 2 Item D2 located?
	<b>Reply:</b> a) Phase 2 - Part "D" - Services - Item 1: Change quantity from 1 to 2. b) Phase 2 - Part "D" - Services - Item 2: Remove item 2. (There is no 150mm diameter service - Form of tender has been changed accordingly.)
<b>12</b>	<b>Question:</b> Can there be an item added for Hydrovac to expose utilities?
	<b>Reply:</b> a) Phase 1 - Part "D" - Services - Items 5: An item for Hydrovac has been added b) Phase 2 - Part "D" - Services - Items 4: An item for Hydrovac has been added.
<b>13</b>	<b>Question:</b> Is there any info on where the gas main or other utilities are?
	<b>Reply:</b> The utilities shown on the plans are what was found during the detailed pickup survey. The contractor will have to call for locates prior to starting the project.
<b>14</b>	<b>Question:</b> What type of material is the existing watermain expected to be? Is it expected to be asbestos?
	<b>Reply:</b> Phase 1 & 2 - Part "B" - Removals - Item 1: The contractor should bid the jobs assuming the existing watermain is not asbestos cement. In the event where a section would be asbestos cement then the City will re-negotiate this removal item with the contractor.
<b>15</b>	<b>Question:</b> Am I understanding correctly that the city will charge tipping fees on all removals disposed of at the city landfill except for clean sand and asbestos pipe?
	<b>Reply:</b> For landfill material dumping and tipping fees, the contractor is invited to refer to section 3.0 paragraph 11(m) of the Special Provisions.
<b>16</b>	<b>Question:</b> Is there more soils information for phase 1? Seems as though the report provided is missing most of the phase 1 area.
	<b>Reply:</b> Soils information; further boreholes information can be found in Appendix "B" for Phase 1
<b>17</b>	<b>Question:</b> Under section 11 special provisions, subsection h says trench to be reinstated with Granular B for full depth unless told by engineer to be backfilled with native. Can we assume that we will be backfilling with native and if not can granular B be extra or provisional?
	<b>Reply:</b> SECTION 3.0 - SCOPE OF WORK Item 11(h) - Watermain Construction • Native compacted material will be accepted from the top of watermain bedding to the road granular "B". The thickness of granular "B" is already defined in the watermain item.
<b>18</b>	<b>Clarification</b>
	<b>THE TENDER SUBMISSION DEADLINE AS BEEN CHANGED TO 2:00:00 P.M. ON THURSDAY APRIL 8, 2021</b>
	<b>END OF ADDENDUM #1</b>